

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20346-00-00
Spot: SWSWNWNW Sec/Twnshp/Rge: 21-34S-43W
1300 feet from N Section Line, 20 feet from W Section Line
Lease/Unit Name: INTERSTATE UNIT Well Number: 86
County: MORTON Total Vertical Depth: 4220 feet

Operator License No.: 4549 Conductor Pipe: Size _____ feet:
Op Name: ANADARKO PETROLEUM CORPORATION Surface Casing: Size 8.625 feet: 1169 WITH 700 SX CMT #137.15
Address: 17001 NORTHCHASE DRIVE Production: Size 5.5 feet: 4218 WITH 250 SX CMT
HOUSTON, TX 77060 Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/05/2001 1:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: TIH W/1-1/4" WS. SPOT 30 SX CMT AT 4200. DISPLACE W/MUD/ SHOOT OFF 5-1/2" CSG AT FREE POINT. SPOT 50 SX CMT AT 1200. TAG PLUG. SPOT 40 SX CMT AT 600. SPOT 10 SX CMT FROM 40 TO SURFACE. CUT OFF AND CAP 8-5/8" CSG 3' BELOW GL.

Plugging Proposal Received By: JIM HOLLAND Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/07/2001 12:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 4161'. PERFS AT 4128-38'. 11/05/01: RUN IN HOLE WITH TUBING TO 3980' & PUMP HULLS & 40 SX CMT. PULL OUT OF HOLE WITH TUBING AND LAY DOWN. SDON. 11/06/01: 1ST PLUG PULL OUT OF HOLE WITH 5 1/2" CASING TO 1200'. LOAD HOLE WITH MUD & PUMP 50 SX CMT. GOOD CIRCULATION. DISPLACE CMT TO BOTTOM WITH MUD. 2ND PLUG PULL OUT OF HOLE WITH 5 1/2" TO 560'. SDON. 11/07/01: LOAD HOLE WITH MUD & PUMP 40 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE WITH CASING TO 40' & PUMP 10 SX CMT TO SURFACE.

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1233' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Jim Holland PERTEN
(TECHNICIAN)

RECEIVED

NOV 21 2001

INVOICED

NOV 13 2001

KCC WICHITA

DATE 11-26-01

INV. NO. 2002060969

Form C-2/3