

1100271
TO: 1-8 API NUMBER 15-129-20,213-0000
STATE CORPORATION COMMISSION 50' FROM W LINE SW/4 SEC. 21, T 34 S, R 43 W

CONSERVATION DIVISION - PLUGGING SECTION 1320 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 50 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME INTERSTATE UNIT WELL # 79

TECHNICIAN'S PLUGGING REPORT COUNTY MORTON

OPERATOR LICENSE # 4549 WELL TOTAL DEPTH 4210 176.83 FEET

OPERATOR: ANADARKO PETROLEUM CORP PRODUCTION CSG: SIZE 5 1/2" @ 4205' WITH 100 SX

NAME AND PO BOX 351 SURFACE CASING: SIZE 8 5/8" @ 1142' WITH 600 SX

ADDRESS LIBERAL, KS 67905-0351 CONDUCTOR CSG: SIZE 20" @ 75' WITH 200 SX

ABANDONED OIL WELL GAS WELL INPUT WELL X SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC LICENSE NUMBER 31151

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 08 MONTH: 01 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT & HORTON PLUGGING INC (PHONE) 405-854-6515

WERE: PERFS AT 4111-17, 4123-29, 4130-35

ON 12-28-98 1ST PLUG RUN COILED TUBING INSIDE 2 7/8" TUBING TO 4111' AND SPOT 100 SX CEMENT.

2ND PLUG CUT OFF TUBING AT 2250' AND SPOT 50 SX AT TUBING STUB. PULL TUBING.

ON 1-8-99 3RD PLUG SPOT 30 SX CEMENT AT 1000' - 900'. 4TH PLUG SPOT 40 SX CEMENT AT 550'.

5TH PLUG SPOT 10 SX CEMENT AT 40-0'. PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART X NONE

OPERATIONS COMPLETED: HOUR: 9:30 AM DAY: 08 MONTH: 01 YEAR: 1999

ACTUAL PLUGGING REPORT

ON 12-28-98 1ST PLUG RUN COILED TUBING INSIDE 2 7/8" TUBING TO 4111' AND SPOT 100 SX CEMENT

2ND PLUG CUT OFF TUBING AT 2250' AND SPOT 50 SX AT TUBING STUB. PULL TUBING.

ON 1-8-99 3RD PLUG SPOT 30 SX CEMENT AT 1000' TO 900'. 4TH PLUG SPOT 40 SX CEMENT AT 550'.

5TH PLUG SPOT 10 SX CEMENT AT 40' TO 0'.

RECEIVED
STATE CORPORATION COMMISSION

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 983' OF 5 1/2" CASING.
HALLIBURTON DID THE CEMENT WORK ON THE FIRST 2 PLUGS. JAN 20 1999

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM) CONSERVATION DIVISION
Wichita, Kansas

I (DID) OBSERVE THIS PLUGGING.

SIGNED *Dan Winter*
(TECHNICIAN) FORM CP-2/3

1-26-99
60578