

To: 1 020803
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-23

API NUMBER 15-NA 15-129-20340-0000

NW NW NW NW, SEC. 21, T 34 S, R 43 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Operator: Anadarko Petroleum Corporation
Name & Address P.O. Box 351
Liberal, KS 67905-0351

40 feet from N & section line

140 feet from W & section line

Lease Name Interstate Unit Well # 83

County Morton

Well Total Depth 4210 136.82 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1169

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: _____ Day: 21 Month: 9 Year: 19 94

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-843-6575

were: 5 1/2" at 4194' w/150 sx cement, PBD 4155', Perfs at 4123-32, 4110-89'

1st plug run tubing and pump 10 sx cement at CIBP at 4002',

2nd plug pump 25 sx cement at 2100',

3rd plug pump 50 sx cement at 1200', 4th plug pump 40 sx cement at 650',

5th plug pump 10 sx cement at 40 to -5'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: _____ Day: 23 Month: 9 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug ran tubing and pumped 10 sx cement at CIBP at 4002',

2nd plug pumped 25 sx cement at 2100',

3rd plug pumped 50 sx cement at 1200',

4th plug pumped 40 sx cement at 650',

5th plug pumped 10 sx cement at 40 to -5'.

Mud between all plugs.

Remarks: Used common cement by Sargent & Horton. Recovered 2138' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED (I () if not) observe this plugging.

DATE OCT 06 1994

WEL. NO. 41314

Signed Glenn R. Barlow
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
OCT 03 1994
CONSERVATION DIVISION
WICHITA, KANSAS