

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20664-00-00
Spot: W2SEW Sec/Twnshp/Rge: 21-34S-43W
3300 feet from S Section Line, 3350 feet from E Section Line
Lease/Unit Name: INTERSTATE UNIT Well Number: 97
County: MORTON Total Vertical Depth: 4250 feet

Operator License No.: 4549 Conductor Pipe: Size _____ feet:
Op Name: ANADARKO PETROLEUM CORPORATION Surface Casing: Size 8.625 feet: 1161 WITH 600 SX CMT *8/138.13*
Address: 17001 NORTHCHASE DRIVE Production: Size 4.5 feet: 4230 WITH 475 SX CMT
HOUSTON, TX 77060 Liner: Size _____ feet:

Well Type: EOR UIC Docket No: E21363.26 Date/Time to Plug: 10/22/2001 10:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 25 SX ON BOTTOM. 1ST PLUG AT 1200' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 10/22/2001 4:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 4224'. PERFS AT 4134-4174'. PUMP 200# HULLS & 20 SX CMT TO PLUG PERFS. 1ST PLUG AT 1200' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 40-0' WITH 10 SX CMT.

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1257' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED

OCT 29 2001

KCC WICHITA

INVOICED

DATE

10-29-01

OCT 23 2001

NV. NO.

2002060868

MP

[Signature]