

1 020354

2-13¹⁵-129-10505-0000, 79 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #E-21,363
C NE NW, SEC. 21, T 34 S, R 43 W/E
4620 feet from S section line
3300 feet from E section line
Interstate Unit
Lease Name _____ Well # 31
County Morton 137.99
Well Total Depth 4246 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 7 feet 1115

TECHNICIAN'S PLUGGING REPORT
Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address P.O. Box 351
Liberal, KS 67905-0351

Abandoned Oil Well _____ Gas Well _____ Input Well SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 1:30 p.m. Day: 12 Month: 2 Year: 19 91

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 4241'w/200 sx cement, CIBP 4133, Perfs at 4153-4188'

1st plug pump 10 sx cement with tubing on top of CIBP at 4133', circulate hole with mud,

2nd plug pump 50 sx cement at 1200-1000',

3rd plug pump 25 sx cement at 650-550',

4th plug pump 10 sx cement at 50-0'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 13 Month: 2 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 10 sx cement with tubing on top of CIBP at 4133, circulated hole with mud,

2nd plug pumped 50 sx cement at 1200-1000',

3rd plug pumped 25 sx cement at 650-550',

4th plug pumped 10 sx cement at 50' to -3'.

RECEIVED STATE CORPORATION COMMISSION

FEB 21 1991 2-21-91

CONSERVATION DIVISION WICHITA, KANSAS

Remarks: Used common cement by Sargent's. Recovered 1202' of 4 1/2" casing. (if additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-25-91

INV. NO. 30825 2-13

Signed Glenn Barlow (TECHNICIAN)