

1100302

TO: STATE CORPORATION COMMISSION

API NUMBER 15-129-20,525 - 0000
E/2 SW NW SEC. 21, T 34 S, R 43 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 685 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME INTERSTATE UNIT WELL # 37A

TECHNICIAN'S PLUGGING REPORT COUNTY MORTON

OPERATOR LICENSE # 4549 WELL TOTAL DEPTH 4260 FEET

OPERATOR: ANADARKO PETROLEUM CORP PRODUCTION CSG: SIZE 4 1/2" @ 4259' WITH NA SX

NAME AND PO BOX 351 SURFACE CASING: SIZE 8 5/8" @ 1160' WITH NA SX

ADDRESS LIBERAL, KS 67905-0351

ABANDONED OIL WELL GAS WELL INPUT WELL E-21, 363 SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC LICENSE NUMBER 31151

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 03 MONTH: 09 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT & HORTON PLUGGING INC (PHONE) 405-854-6515

WERE: PERFS AT 4120-4173

PUMP 3 SX HULLS AND 15 SX CEMENT AND DISPLACE WITH 9# MUD. LOAD HOLE WITH 9# MUD.

PULL FREE POINT AND SHOOT OFF 4 1/2" CASING. TOH TO 1235'. SPOT 80 SX CEMENT FROM

1062. TOH W/CASING. SPOT 10 SX CEMENT FROM 30-3.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:30 PM DAY: 03 MONTH: 09 YEAR: 1999

ACTUAL PLUGGING REPORT

ON 9-1-99 1ST PLUG SPOT 20 SX CEMENT WITH 100# HULLS AT 4120' WITH 500 PSI AT END OF

DISPLACEMENT. CIRCULATE HOLE WITH 9# MUD. GOOD RETURNS. 2ND PLUG SPOT 50 SX CEMENT

AT 2641'. GOOD CIRCULATION. 3RD PLUG SPOT 50 SX CEMENT AT 1200'. GOOD CIRCULATION.

4TH PLUG SPOT 40 SX CEMENT AT 550'. GOOD CIRCULATION. 5TH PLUG SPOT 15 SX CEMENT AT

50' TO 0'.

REMARKS USED COMMON CEMENT BY SARGENTS. RECOVERED 2700' OF 4 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

DATE 9-24-99
(DID) OBSERVE THIS PLUGGING.

INV. NO. 20000608

SIGNED Gary Winters by SAM
(TECHNICIAN) FORM CP-2/3

RECEIVED
KANSAS CORP COM
1999 SEP 17 1:04 PM

138.45