

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-20257-00-00  
Spot: CW2 Sec/Twnshp/Rge: 21-34S-43W  
2640 feet from S Section Line, 3960 feet from E Section Line  
Lease/Unit Name: INTERSTATE UNIT Well Number: 81  
County: MORTON Total Vertical Depth: 4230 feet

Operator License No.: 4549 Conductor Pipe: Size feet: 134.48  
Op Name: ANADARKO PETROLEUM CORPORATIO Surface Casing: Size 8.625 feet: 1125 WITH 700 SX CMT  
Address: 17001 NORTHCHASE DRIVE Production: Size 5.5 feet: 4230 WITH 100 SX CMT  
HOUSTON, TX 77060 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/31/2001 3:00 PM

Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 200# HULLS & 40 SX CMT ON BOTTOM. 1ST PLUG AT 1200' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 11/02/2001 4:30 PM

KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 4198'. PERFS AT 4130-4146'. PUMP 200# HULLS & 40 SX CMT FOR BOTTOM PLUG. DISPLACE TO BOTTOM WITH MUD & PRESSURED TO 300 PSIG. SDON. 11/01/01: RUN IN HOLE WITH TUBING TO BOTTOM. SPUD THROUGH BRIDGE @ 2150-2200'. RUN 130 JOINTS TBG IN HOLE TO 4100', PUMP BOTTOM PLUG AGAIN WITH 40 SX CMT. PULL OUT OF HOLE WITH TUBING. SDON. 11/02/01: PULL OUT OF HOLE TO 1160'. LOAD HOLE WITH MUD & PUMP 50 SX CMT. PULL OUT OF HOLE TO 560'. LOAD HOLE WITH MUD. PUMP 40 SX CMT. PULL OUT OF HOLE TO 40'. PUMP 10 SX CMT.

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1233' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Jim Holland  
(TECHNICIAN)

[Signature]

RECEIVED

NOV 06 2001

KCC WICHITA

INVOICED

NOV 05 2001

Form CP-2/3

DATE 11-7-01

INV. NO. 2002060916

MP