

TO: -
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20562-00-00
Spot: SW Sec/Twnshp/Rge: 21-34S-43W
1320 feet from S Section Line, 1320 feet from W Section Line
Lease/Unit Name: INTERSTATE UNIT Well Number: 92
County: MORTON Total Vertical Depth: 4270 feet

Operator License No.: 4549 Conductor Pipe: Size _____ feet: 8 138.78
Op Name: ANADARKO PETROLEUM CORPORATION Surface Casing: Size 8.625 feet: 1163 WITH 700 SX CMT
Address: 17001 NORTHCHASE DRIVE Production: Size 5.5 feet: 4270 WITH 120 SX CMT
HOUSTON, TX 77060 Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/26/2001 9:30 AM

Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 100# HULLS & 25 SX CMT TO PLUG BOTTOM. 1ST PLUG AT 1200' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG
Date/Time Plugging Completed: 10/31/2001 3:00 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 4227'. PERFS AT 4122-4128'. 10/26/01: PUMPED 100# HULLS & 25 SX CMT THROUGH CASING TO PLUG BOTTOM. DID NOT HOLD. RUN IN HOLE WITH TUBING TO PBTD. PLUG WENT SOUTH. SDON. 10/29/01: RAN IN HOLE WITH 2 3/8" TUBING & SPOT 50 SX CMT ON BOTTOM. PULL OUT OF HOLE WITH TUBING. SDON. 10/30/01: 1ST PLUG PULL OUT OF HOLE TO 1200'. LOAD HOLE WITH MUD. PUMP 50 SX CMT. 2ND PLUG PULL OUT OF HOLE TO 600'. LOAD HOLE WITH MUD. PUMP 40 SX CMT. 10/31/01: PULL OUT OF HOLE TO 40' & PUMP 10 SX CMT.

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1370' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Jim Holland (TECHNICIAN)

RECEIVED
NOV 06 2001
KCC WICHITA

INVOICED
DATE 11-7-01
INV. NO. 2002060916

NOV 05 2001

NP