

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-20564-00-00  
Spot: SWSW Sec/Twnshp/Rge: 21-34S-43W  
85 feet from S Section Line, 1200 feet from W Section Line  
Lease/Unit Name: INTERSTATE UNIT Well Number: 94  
County: MORTON Total Vertical Depth: 4245 feet

Operator License No.: 4549 Conductor Pipe: Size feet: \$137.96  
Op Name: ANADARKO PETROLEUM CORPORATION Surface Casing: Size 8.625 feet: 1169 WITH 650 SX CMT  
Address: 17001 NORTHCHASE DRIVE Production: Size 5.5 feet: 4244 WITH 180 SX CMT  
HOUSTON, TX 77060 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/24/2001 12:30 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 4070'. SPOT 10 SX CMT BY RUNNING 1 1/4" IN HOLE. 1ST PLUG AT 1200' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 10/25/2001 10:00 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:  
PBTD 4209'. PERFS AT 4119-4133'. CIBP @ 4070'. CIRCULATE HOLE WITH MUD. RUN IN HOLE WITH WORKING STRING & SPOT 10 SX CMT ON TOP OF CIBP. 1ST PLUG PULL OUT OF HOLE WITH CASING TO 1200' & PUMP 50 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE WITH CASING TO 600' & SPOT 40 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. PULL OUT OF HOLE WITH CASING. SDON. 10/25/01; PUMP 10 SX AT 40'.

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2200' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Jim Holland  
(TECHNICIAN)

RECEIVED  
NOV 06 2001  
KCC WICHITA

INVOICE  
DATE 11-7-01  
NOV 05 2001  
2002060916

Form CP-233