

To: 1 020470 7-2
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Operator: Anadarko Petroleum Corp.
Name: P.O. Box 351
Address: Liberal, KS 67905-0351

Abandoned Oil Well Gas Well ENHR

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 2:30 p.m. Day: 30 Month: 6 Year: 1992

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 4220' w/600 sx cement, PBTD 4184', Perfs at 4154-69'

1st plug release packer and pump 1 sx hulls and 20 sx cement at perfs, load hole with mud,

2nd plug pump 40 sx cement at 1175-1050', displace with mud,

3rd plug pump 35 sx cement at 650-550',

4th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn R. Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 12 p.m. Day: 2 Month: 7 Year: 1992

ACTUAL PLUGGING REPORT 1st plug released packer and pumped 1 sx hulls and 20 sx cement at
perfs, loaded hole with mud,

2nd plug pumped 40 sx cement at 1175-1050', displaced with mud,

3rd plug pumped 35 sx cement at 650-550',

4th plug pumped 10 sx cement at 40 to -4'.

Remarks: Used common cement by Sargent's. Recovered 1222' of 5 1/2" casing.

(if additional description is necessary, use BACK of this form.)

I (did / XXXXXX) observe this plugging.

DATE 8-6-92

INV. NO. 35868

15-129-10405-0000 API NUMBER 15- Drilled 9/13/55 Docket / #E-21,363

SW SE, SEC. 20, T. 34 S, R. 43 W/EX

660 feet from S section line

1980 feet from E section line

Lease Name Interstate Unit Well # 47

County Morton

Well Total Depth 4270 138.77 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1153

ENHR X SHD Well D&A

RECEIVED
STATE CORPORATION COMMISSION
JUL 7 1992
CONSERVATION DIVISION
Wichita, Kansas

Signed Glenn R. Barlow
(TECHNICIAN)