

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-129-20,609-0000  
\_\_\_\_\_, Sec. 20, T 34 S, R 43 (W/E)

TECHNICIAN'S PLUGGING REPORT

1320 feet from ~~N~~ section line  
660 feet from ~~XX~~/E section line

Operator License # 5469

Lease Name Interstate Well # F-6

Operator: Anadarko Production Co.  
Name & P. O. Box 351  
Address Liberal, KS 67901

County Morton

316-624-6253

*called  
3-2-84*

Well Total Depth 5400 feet 175.50

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1168

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargents Casing Pullers Service License Number 6547

Address 620 South Lincoln, Liberal, KS 67901

Company to plug at: Hour: 12:15 pm Day: 27 Month: January Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Doug Blair

(company name Sargents (phone) 316-624-7455

were: Pumped 1 sack hulls, 35 sx cement to bottom covering the perfs. Filled hole with heavy mud. Shot pipe off at 1034' and pumped 45 sx cement through 4 1/2 production pipe. 3rd plug - pumped 40 sx cement through production pipe to 700'. 4th plug build solid bridge at 40' and filled hole to surface with 10 sx cement.

Signed Paul A. Luthie  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 2:00 pm Day: 27 Month: January Year: 19 84

ACTUAL PLUGGING REPORT Pumped 1 sack hulls, 35 sx cement to bottom covering the perfs. Filled hole with heavy mud. Shot pipe off at 1034' and pumped 45 sx cement through 4 1/2 production pipe. 3rd plug - pumped 40 sx cement through production pipe to 700'. 4th plug build solid bridge at 40' and filled hole to surface with 10 sx cement.

Remarks: Used sacked common cement. by Sargents Casing Pullers Service they recovered 1034' of 4 1/2 production pipe.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 02 1984  
CONSERVATION DIVISION  
Wichita, Kansas

2-2-84

I hereby certify that the above plugging instructions were given as herein stated and that I (~~did~~ / did not) observe this plugging.

Signed Paul A. Luthie  
(TECHNICIAN)

INVOICED  
DATE 2-6-84  
INV. NO. 0058

1-27