

11-11 15-129-10401-0000

1 020268

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 3/9/56

C NE NW, SEC. 20, T 34 S, R 43 WXE

4620 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name ISU Well # 27

Operator: Anadarko Petroleum Corporation
Name &

County Morton 138.61

Address P.O. Box 351

Well Total Depth 4265 feet

Liberal, KS 67905-0351

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1119

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 South Lincoln, Liberal, KS 67901

Company to plug at: Hour: 4 p.m. Day: 8 Month: 11 Year: 1989

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 4265' CIBP at 4090' DV tool at 3106' TOC 2150' Perfs at 4192-4212'

1st plug set CIBP at 4090' with 20 sx cement on top with tubing,

2nd plug pump 25 sx cement at 2015', 3rd plug pump 50 sx cement at 1250-1100',

4th plug pump 35 sx cement from 650-480',

5th plug pump 10 sx cement at 40-0'. Heavy mud between all plugs.

Plugging Proposal Received by Glenn R. Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 4:30 p.m. Day: 11 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4090' with 20 sx cement on top with tubing,

2nd plug pumped 25 sx cement at 2015',

3rd plug pumped 50 sx cement at 1250-1100',

4th plug pumped 35 sx cement from 650-480',

5th plug pumped 10 sx cement at 40-0'. Heavy mud between all plugs.

RECEIVED
STATE CORPORATION COMMISSION
NOV 27 1989
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 2015' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-5-89
INV. NO. 26620
11-11

observe this plugging.

Signed Glenn R. Barlow
(TECHNICIAN)