

To: 1 020653
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-129-20,343-0000
NE SW NE, SEC. 20, T. 34 S, R. 43 W/EX
1650 feet from N & section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name &
Address P.O. Box 351
Liberal, KS 67905-0351

Lease Name Interstate Unit Well # 85
County Morton
Well Total Depth 4230 137.47 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 951

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 11 a.m. Day: 1 Month: 4 Year: 19 93

Plugging proposal received from Don Horton
(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 4 1/2" at 4222' w/140 sx cement, PBSD 4221', Perfs at 4166-74'
1st plug pump 1 sx hulls and 25 sx cement at perfs and load hole with mud,
2nd plug pump 50 sx cement at 830',
3rd plug pump 30' sx cement at 475',
4th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 10 a.m. Day: 3 Month: 4 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 25 sx cement at perfs, loaded hole
with mud,
2nd plug pumped 50 sx cement at 830',
3rd plug pumped 30 sx cement at 475',
4th plug pumped 10 sx cement at 40 to -4'.
Mud between all plugs.

Remarks: Used common cement by Sargent & Horton. Recovered 830' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
APR 14 1993

INVOICED
DATE 4-15-93
NO. 37571
4-3

Signed Glenn Barlow
(TECHNICIAN)