

15-129-10414-0000
9-27-Docket #E-11,602

To: 1 050933
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Completion date 1/14/56
C NW SW, SEC. 20, T 34 S, R 43 W/E
1980 feet from S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

4620 feet from E section line
Interstate Unit
Lease Name Well # 39

Operator: Anadarko Petroleum Corporation
Name & Address P.O. Box 351

County Morton 138.45
Well Total Depth 4260 feet

Liberal, KS 67905-0351

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1140

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 South Lincoln, Liberal, KS 67901

Company to plug at: Hour: 8 a.m. Day: 26 Month: 9 Year: 19 87

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 4259' PBD 4223' Perfs at 4180-87, 4194-4212'

1st plug pump 1 sx hulls and 50 sx cement at 4200',

2nd plug at 1135' with 70 sx cement,

3rd plug at 600' with 35 sx cement,

4th plug at 40-0' with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5 a.m. Day: 27 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 50 sx cement at 4200',

2nd plug at 1135' with 70 sx cement,

3rd plug at 600' with 35 sx cement,

4th plug at 40-0' with 10 sx cement.

RECEIVED STATE CORPORATION COMMISSION

OCT 2 1987 10-2-87

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 1135' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED
I (check) did not observe this plugging.

Signed Richard W. Lacey (TECHNICIAN)

DATE 10-6-87

INV. NO. 18369

09-27 OCT 29 1987