

1-23 15-129-10377-00995
295
P

To: 1 020290
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- E-11,602
C SE SW, SEC. 20, T 34 S, R 43 W/E
660 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address: P.O. Box 351
Liberal, KS 67905-0351

Lease Name Interstate Unit Well # 46
County Morton 136.34
Well Total Depth 4195 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1216

Abandoned Oil Well Gas Well Input Well X SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 11 a.m. Day: 18 Month: 1 Year: 1990

Plugging proposal received from Don Horton

(company name) Sargent's (phone) 316-624-7455

were: 5 1/2" at 4195' PRT'D 4175' Perfs at 4152-74'

- 1st plug pump 1 sx hulls and 25 sx cement at perfs, displace with mud,
- 2nd plug pump 35 sx cement at 2600',
- 3rd plug pump 50 sx cement at 1650',
- 4th plug pump 35 sx cement at 650', 5th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn R. Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:45 a.m. Day: 23 Month: 1 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 25 sx cement at perfs, displaced with mud,

- 2nd plug pumped 35 sx cement at 2600',
- 3rd plug pumped 50 sx cement at 1650',
- 4th plug pumped 35 sx cement at 650',
- 5th plug pumped 10 sx cement at 40 to -4',

Remarks: Used common cement by Sargent's. Recovered 2626' of 5 1/2" casing. additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
JAN 30 1990
1-30-90
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE FEB 05 1990 observe this plugging.

Signed Glenn R. Barlow (TECHNICIAN)

INV. NO. 27305
1-23