

15-129-10403-0000
11-15

1020267

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Docket #E-11,602
C SW NW, SEC. 20, T 34 S, R 43 W/E
3300 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address P.O. Box 351
Liberal, KS 67905-0351

Lease Name Interstate Unit Well # 33
County Morton 137.80
Well Total Depth 4240 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1115

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 South Lincoln, Liberal, KS 67901

Company to plug at: Hour: 10 a.m. Day: 14 Month: 11 Year: 19 89

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 2301', 5 1/2" at 4239' TOC 2000' PBD 4209' Perfs at 4170-90' DV tool at 3174'
Cmt. Circ to Surface,

- 1st plug load hole with heavy mud and pump 50 sx cement at perfs to 3800',
- 2nd plug pump 35 sx cement at 2500-1900',
- 3rd plug pump 20 sx cement at 1390-920', 4th plug spot 20 sx cement from 650-270',
- 5th plug pump 5 sx cement from 75-0'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 3:30 p.m. Day: 15 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug loaded hole with heavy mud, pumped 50 sx cement at
perfs to 3800',

- 2nd plug pumped 35 sx cement at 2500-1900',
- 3rd plug pumped 20 sx cement at 1390-920',
- 4th plug spot 20 sx cement at 650-270',
- 5th plug spot 5 sx cement from 75-0'.

Remarks: Used common cement by Sargent's. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED

(did / observe) observe this plugging.

DATE 12-5-89

Signed Glenn P. Barlow
(TECHNICIAN)

INV. NO. 216619
11-15

RECEIVED
STATE CORPORATION COMMISSION
NOV 27 1989
CONSERVATION DIVISION
Wichita, Kansas