

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-10412-00-00  
Spot: SENE Sec/Twnshp/Rge: 20-34S-43W  
1980 feet from N Section Line, 660 feet from E Section Line  
Lease/Unit Name: INTERSTATE UNIT Well Number: 36  
County: MORTON Total Vertical Depth: 4612 feet

Operator License No.: 4549 Conductor Pipe Size: 13.375 feet: 69 WITH 100 SX CMT  
Op Name: ANADARKO PETROLEUM CORPORATI Production Casing Size: 5.5 feet: 4204 WITH 600 SX CMT  
Address: 1201 LAKE ROBBINS DRIVE Surface Casing Size: 8.625 feet: 1082 WITH 600 SX CMT  
THE WOODLANDS, TX 77380 8149.89

Well Type: EOR UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/28/2003 3:00 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: JOHN Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed  
Plugging  
Method:

CIBP @ 4100' WITH 2 SX CMT. 50 SX CMT AT 1110'. 40 SX CMT AT 500'. 10 SX CMT AT 40'.

Plugging Proposal Received By: STEVE MIDDLETON  
Date/Time Plugging Completed: 08/28/2003 5:00 PM

Witness Type: Plugging Operations Were Not Witnessed  
KCC Agent: JIM HOLLAND

Actual Plugging Report:


PBTD 4206'. PERFS AT 4158-4182'. SET CIBP @ 4100'. DID NOT SET. LOST DOWNHOLE. SET 2ND CIBP @ 3990' WITH 2 SX CMT ON TOP. 1ST PLUG PULL OUT OF HOLE TO 1110'. LOAD HOLE WITH MUD & PUMP 50 SX CMT. 2ND PLUG PULL OUT OF HOLE TO 500'. LOAD HOLE & PUMP 40 SX CMT. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

RECEIVED  
SEP 17 2003  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1137' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed Jim Holland PERTA  
(TECHNICIAN)

INVOICED  
DATE 9-17-03  
INV. NO. 2004060576

Form CP-2/3