

15-129-10408-0000  
9-28-87

To: 1 061019  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-Drill completion 11/11/55  
C SE NW, SEC. 20, T 34 S, R 43 W/E  
3300 feet from S section line  
3300 feet from E section line  
Interstate Unit  
Lease Name \_\_\_\_\_ Well # 34

TECHNICIAN'S PLUGGING REPORT  
Operator License # 4549  
Operator: Anadarko Petroleum Corporation  
Name & Address P.O. Box 351  
Liberal, KS 67905-0351

County Morton 170.69  
Well Total Depth 4552 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1193

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling Service License Number 6547  
Address 620 South Lincoln, Liberal, KS 67901

Company to plug at: Hour: 8 a.m. Day: 28 Month: 9 Year: 19 87

Plugging proposal received from Doug Blair  
(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 4300' PBTB at 4060' w/CIBP Perfs at 4172-98' DV tool at 3214'  
1st plug set CIBP at 4060' with 25 sx cement on top,  
2nd plug at 1200' with 70 sx cement,  
3rd plug at 650' with 35 sx cement,  
4th plug at 40-0' with 10 sx cement.

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None   
Operations Completed: Hour: 4 p.m. Day: 28 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4060' and dumped 25 sx cement on top,  
2nd plug at 1200' with 70 sx cement,  
3rd plug at 650' with 35 sx cement,  
4th plug at 40-0' with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 2 1987  
10-2-87  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 1212' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
I hereby do hereby observe this plugging.

Signed Paul A. Luthi  
(TECHNICIAN)

DATE 10-6-87

INV. NO. 18371

9-2 OCT 29 1987