

1020848 3-16

API NUMBER 15-129-20,454 - 0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

W/2 SW NE SE, SEC. 20, T 34 S, R 43 W/E
1650 feet from S section line
1250 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Interstate F Well # 3

Operator: Anadarko Petroleum Corporation
Name & Address P.O. Box 351
Liberal, KS 67905-0351

County Morton
Well Total Depth 1330 43.23 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 378

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 10 a.m. Day: 16 Month: 3 Year: 19 95

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 4 1/2" at 1330' w/500 sx cement, PBSD 1324', Perfs at 1179-88, 1194-1210'

1st plug pump 1 sx hulls and 20 sx cement at perfs with tubing, displace with mud,

2nd plug pump 30 sx cement at 600',

3rd plug pump 3 sx cement in 4 1/2" and fill 8 5/8" to surface with app. 3 sx.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:30 p. Day: 16 Month: 3 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement at perfs with tubing, displaced with mud,

2nd plug pumped 30 sx cement at 600',

3rd plug pumped 3 sx cement in 4 1/2" and filled 8 5/8" to surface with app. 3 sx cement.

Remarks: Used common cement by Sargent & Horton. No casing recovery.
(if additional description is necessary, use BACK of this form.)

Observe this plugging.

DATE MAR 29 1995

INV. NO. 42478

Signed Glenn R Barlow (TECHNICIAN)

STATE CORPORATION COMMISSION RECEIVED
MAY 2 1995