

To: 1 020639 1-14
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-129-20,405-0000 113 R
C SW, SEC. 19, T 34 S, R 43 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5156
Operator: Edger W. White
Name & Address 701 Vilymaca St.
Elkhart, KS 67950

1320 feet from S section line
3960 feet from E section line
Lease Name Interstate Red Cave Well # 4
County Morton 41.43
Well Total Depth 1275 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 409

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling License Number 6547
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 10 a.m. Day: 14 Month: 1 Year: 19 93

Plugging proposal received from Doug Blair
(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 4 1/2" at 1274' w/250 sx cement, Perfs at 1223-43'
1st plug run tubing to 720' and pump 1 sx hulls and 20 sx cement,
2nd plug pump 1/2 sx gel and 25 sx cement at 430',
3rd plug pump 5 sx cement at 40 to -4'.
Check backside.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 3:30 p.m. Day: 14 Month: 1 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug ran tubing to 720', stacked out. Pumped 1 sx hulls and 20
sx cement,
2nd plug pumped 1/2 sx gel and 25 sx cement at 430',
3rd plug pumped 5 sx cement at 40 to -4'.
Checked backside-O.K.

RECEIVED
STATE CORPORATION COMMISSION
JAN 21 1993 1-21-93
CONSERVATION DIVISION
WICHITA, KANSAS

4 1/2" had collapsed at approx. 775'. They tried to mill down but milled out of side of pipe.
Was then abandoned by Edger White.

Remarks: Used common cement by Sargent's. No casing recovery.
(If additional description is necessary, use BACK of this form.)

I (old / new copy) observe this plugging.

DATE FEB 16 1993
INV. NO. 37334

Signed Glenn R Barlow
(TECHNICIAN)