

15-129-10393-0000

1-100034

3-25

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
WICHITA STATE OFFICE BUILDING  
WICHITA, KANSAS 67202

API number: Drill completion 5/21/54  
C NE NE SEC. 18, 34 S, 43 W  
4620 feet from S section line  
660 feet from E section line

Operator license# 3877

Lease Government well # 1

Operator: Executive Properties, Inc. County Morton

Address: 1715 W. 58th

Amarillo, TX 79110

Well total depth 4665 feet  
Conductor Pipe:        inch @        feet  
Surface pipe: 9 5/8 inch @ 520 feet

151.61

Aband. Oil well    , Gas well X, Input well    , SWD    , D & A    

Plugging contractor: Sargent & Horton Plugging Service License# 31151

Address: Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 12:00 p.m. Day: 22 Month: March Year: 1996

Plugging proposal received from: Don Horton

Company: Sargent & Horton Plugging Service Phone: 405-854-6515

Were: 5 1/2" at 3503', Perfs at 2807-3008'

1st plug pump 25 sx cement and 4 sx hulls on bottom.

2nd plug pump 75 sx cement at 580',

3rd plug pump 10 sx cement at 40'.

Plugging Proposal Received by: Gary Winters

Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 12:00 p.m. Day: 25 Month: March Year: 1996

Actual plugging report:

3/22/96

1st plug set 25 sx cement and 4 sx hulls from 2828-2628'. Allowed plug to set over weekend.

3/25/96

2nd plug cut off at 900', circulated hole to surface and pulled pipe to 580' and set a 75 sx plug.

3rd plug pulled to 40' and set 10 sx cement from 40-0'.

Remarks: Used common cement by Sargent & Horton. Recovered 900' of 5 1/2" casing.

I did[X] / did not[     ] observe the plugging.

Gary Winters  
(agent)

Form CP-2/3

**INVOICED**

DATE 4-16-96

INV. NO. 45300

RECEIVED  
KANSAS CORP COMM  
1996 APR -9 A 11:34

*[Handwritten mark]*