

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20400-00-00
Spot: CSE Sec/Twnshp/Rge: 18-34S-43W
1320 feet from S Section Line, 1320 feet from E Section Line
Lease/Unit Name: INTERSTATE Well Number: B2-18
County: MORTON Total Vertical Depth: 3548 feet

Operator License No.: 5156
Op Name: WHITE, EDGAR W.
Address: 701 VILYMACA ST.
ELKHART, KS 67950

Conductor Pipe: Size feet: \$115.31
Surface Casing: Size 8.625 feet: 415 WITH 375 SX CMT
Production: Size 5.5 feet: 3548 WITH 500 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 08/26/2002 10:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PLUG AT 2100' WITH 25 SX CMT. PULG AT 1300' WITH 25 SX CMT. PLUG AT 430' CIRCULATE TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/26/2002 3:30 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 2650'. PERFS AT 1264-72 & 2560-64'. WLTC RETRIEVABLE BP @ 2500' WITH 10 JOINTS OF TUBING TO 2157'. RUN IN HOLE WITH 2 3/8" TUBING TO 2150' & PUMP 100# HULLS WITH 25 BBL MUD. 1ST PLUG PUMP 25 SX CMT AT 2150'. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE WITH TUBING TO 1300'. LOAD HOLE WITH MUD & PUMP 100# HULLS WITH 25 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE WITH TUBING TO 430' & PUMP 48 SX CMT TO SURFACE INSIDE 5 1/2". HOOK TO BACKSIDE AND PUMP 10 SX CMT. PRESSURE TO 500 PSIG & SHUT IN.

RECEIVED
SEP 19 2002
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: TBG

District: 01

Signed Jim Holland PERTH
(TECHNICIAN)

INVOICED SEP 16 2002
DATE 9-19-02
WEL NO. 2003060536 MP

Roth SP-213