

To: **1 020802** **15-129-10395-0000** **9-28**  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER **15-** Spud date 5/14/57

C NE NE, SEC. 17, T 34 S, R 43 W/E

4620 feet from S section line

660 feet from E section line

Lease Name Government A 2  
Interstate Unit Well # 10

County Morton 142.67

Well Total Depth 4390.5 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1200

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Operator: Anadarko Petroleum Corporation  
Name & Address P.O. Box 351  
Liberal, KS 67905-0351

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 10 a.m. Day: 26 Month: 9 Year: 19 94

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6575

- were: 5 1/2" at 4390.5' w/150 sx cement, PBTD 4356', Perfs at 4293-98, 4312-27'  
1st plug CIBP set at 4110' with 10 sx cement on top with tubing;  
2nd plug pump 50 sx cement at 1250',  
3rd plug pump 40 sx cement at 650',  
4th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn R. Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 10 a.m. Day: 28 Month: 9 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4110' with 10 sx cement on top with tubing,

2nd plug pumped 50 sx cement at 1250',

3rd plug pumped 40 sx cement at 650',

4th plug pumped 10 sx cement at 40 to -4'.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 03 1994

CONSERVATION DIVISION  
WICHITA, KANSAS

Remarks: Used common cement by Sargent & Horton. Recovered 1258' of 5 1/2" casing.  
(If additional description is necessary, use **BACK** of this form.)

**INVOICED** (copy to ~~XXXXXX~~) observe this plugging.

DATE OCT 06 1994  
REV. NO. 41215

Signed Glenn R. Barlow  
(TECHNICIAN)