

1 020761

15-129-10498-0000
5-25

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15 - Spud Date 2/12/58
C NE SE, SEC. 17, T 34 S, R 43 W/4
1980 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address: P.O. Box 351
Liberal, KS 67905-0351

Lease Name Interstate Unit Well # 17
County Morton
Well Total Depth 4340 ^{141.05} feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 7" feet 1248

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151
Address Rt. 1, Box 49BA, Tyrone, KS 73951-9731

Company to plug at: Hour: 1 p.m. Day: 21 Month: 5 Year: 19 94

Plugging proposal received from Don Horton
(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6575

logs: 4 1/2" at 4319' w/125 sx cement, PBTD 4282', Perfs at 4239-56'
1st plug set CIBP at 4136', 2nd plug pump 1 sx hulls and 20 sx cement at 4136',
3rd plug pump 25 sx cement at 2523', 4th plug pump 45 sx cement at 1345',
5th plug pump 25 sx cement at 650', 6th plug pump 10 sx cement at 52' to -4'.
Mud between all plugs.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 25 Month: 5 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4136',

2nd plug pumped 1 sx hulls and 20 sx cement at 4136',
3rd plug pumped 25 sx cement at 2523',
4th plug pumped 45 sx cement at 1345',
5th plug pumped 25 sx cement at 650',
6th plug pumped 10 sx cement at 52 to -4'. Mud between all plugs.

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 31 1994
CONSERVATION DIVISION
WICHITA, KS

Remarks: Used common cement by Sargent & Horton Plugging. Recovered 2523' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

(said ~~XXXXXX~~) observe this plugging.

DATE 6-6-94
INV. NO. 40529
5-25

Signed Glenn R Barlow
(TECHNICIAN)