

To: 1 020654
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200, COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-129-20-557-0000
C SE/4, SEC. 17, T. 34 S, R. 43 W/XX

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

1320 feet from S section line
1320 feet from E section line

Operator: Anadarko Petroleum Corporation
Name:
Address P.O. Box 351
Liberal, KS 67905-0351

Lease Name Interstate Unit Well # 87
County Morton 139.10

Well Total Depth 4280 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1205

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 9 a.m. Day: 4 Month: 4 Year: 1993

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

was: 4 1/2" at 4280' w/175 sx cement. PBTB 4100', Perfs at 4171-78'

1st plug pump 1 sx hulls and 20 sx cement at 4100', load hole with mud,

2nd plug pump 30 sx cement at 2500',

3rd plug pump 40 sx cement at 1240', 4th plug pump 30 sx cement at 650',

5th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 11 a.m. Day: 7 Month: 4 Year: 1993

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement through cement retainer
at 4100', loaded hole with mud,

2nd plug pumped 30 sx cement at 2500',

3rd plug pumped 40 sx cement at 1240',

4th plug pumped 30 sx cement at 650',

5th plug pumped 10 sx cement at 40 to -4'.

RECEIVED
STATE CORPORATION COMMISSION

APR 14 1993

Remarks: Used common cement by Sargent & Horton. Recovered 2535' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

~~did not observe this plugging.~~

DATE 4-15-93

Signed Glenn Barlow
(TECHNICIAN)

INV. NO. 37570