

1 020028

15-129-10487-000076 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket # 11,602

C SW NE, SEC. 17, T 34 S, R 43 (W) 8

3300 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Interstate Unit Well # 13

Operator: Anadarko Petroleum Corporation
Name & Address: P.O. Box 351,
Liberal, KS 67901

County Morton 14.90

Well Total Depth 4366 feet

Conductor Pipe: Size feet

Surface Casing: Size 7" feet 1200

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 S. Lincoln, Box 506, Liberal, KS 67901

Company to plug at: Hour: 10 a.m. Day: 16 Month: 9 Year: 1986

Plugging proposal received from Kirby Lillard

(company name) Sargent's (phone) 316-624-7455

were: 4 1/2" at 4366' PBD 4330 Perfs at 4246-4276

1st plug CIBP at 4200' with 20 sx cement on top

2nd plug at 2870' with 30 sx cement

3rd plug at 1300' with 35 sx cement

4th plug at 650' with 25 sx cement

5th plug at 40-0' with 10 sx cement

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 5 p.m. Day: 16 Month: 9 Year: 1986

ACTUAL PLUGGING REPORT Heavy mud spotted between all plugs

1st plug CIBP at 4200' with 20 sx cement using tubing

2nd plug at 2870' with 30 sx cement

3rd plug at 1300' with 35 sx cement

4th plug at 650' with 25 sx cement

5th plug at 40-0' with 10 sx cement

Remarks: Recovered 2903' 4 1/2" casing. Used common cement by Sargent's.

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 9-19-86

9-18-86

Signed [Signature] (TECHNICIAN)

INV. NO. 14975

SEP 18 1986