

15-129-10485-0000

1 020031

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-Docket # C-21,363  
C NW SE, SEC. 17, T 34 S, R 43 W/E  
1980 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549  
Operator: Anadarko Petroleum Corporation  
Name & Address P.O. Box 351  
Liberal, KS 67901

Lease Name Interstate Unit Well # 16  
County Morton 141.08  
Well Total Depth 4341 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 7 feet 1264

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well X D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargents Casing Pulling Service License Number 6547

Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 1:10 p.m. Day: 18 Month: 9 Year: 19 86

Plugging proposal received from Kirby Lillard

(company name) Sargents (phone) 316-624-7455

were: 4 1/2" at 4340 PBTD 4298 Perfs at 4236-4266

- 1st plug set CIBP at 4200' and pump 20 sx cement through tubing on top of CIBP
- 2nd plug load hole with lease mud, spot 20 sx cement at 2900' through tubing
- 3rd plug shoot off casing and spot 25 sx cement on stub
- 4th plug 25' sx cement at 650', 5th plug 10 sx cement at 70'

Plugging Proposal Received by Don Ubel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5 p.m. Day: 18 Month: 9 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug CIBP at 4200' with 20 sx cement, squeezed at 2900-2820'

- with 375 sx cement
- 2nd plug at 2600' with 20 sx cement spotted through tubing
- 3rd plug at 1300' with 35 sx cement spotted through 4 1/2"
- 4th plug at 650' with 25 sx cement
- 5th plug at 70'-below GL with 10 sx cement Hole was filled with heavy mud before spotting plugs.

Remarks: Used common cement by Sargents. Recovered 1530' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

DATE 9-24-86 9-24-86  
SEP 24 1986

Signed [Signature]  
(TECHNICIAN)

INV. NO. 15010  
9-18