

1-3-88 15-129-10396-0000

To: 1020115
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 7/24/57
C NW NE, SEC. 17, T 34 S, R 43 W XX
4620 feet from S section line
1980 feet from E section line
Interstate Unit
Lease Name _____ Well # 9

TECHNICIAN'S PLUGGING REPORT
Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address: P.O. Box 351
Liberal, KS 67901

County Morton 152.26
Well Total Depth 4385 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1243

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 South Lincoln, Liberal, KS 67901

Company to plug at: Hour: 9:30 a.m. Day: 30 Month: 12 Year: 19 87

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 4385' PBSD 4100' Perfs at 4298-4332' Elevation 3581' GL

1st plug set CIBP at 4100, dump 20 sx cement on top of CIBP, 2nd plug spot cement plug at casing cut with 30 sx cement,

3rd plug pump 60 sx cement at 1325-1175', 4th plug pump 70 sx cement from 650-480',

5th plug pump 26 sx cement from 50-0'. Spot mud between plugs.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 3 Month: 1 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4100' with 20 sx cement on top of plug,

2nd plug pumped 30 sx cement at 2400',

3rd plug pumped 60 sx cement at 1325-1085',

4th plug pumped 70 sx cement at 650-370',

5th plug pump 20 sx cement at 50-0'. 1-14-88 JAN 14 1988

Heavy mud between plugs.

Remarks: Used common cement by Sargent's. Recovered 2416' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-15-88
INV. NO. 19577

Signed Glen R. Barlow (TECHNICIAN)