

15-119-20017-0000

FORM - CP-2  
Rev. 9-8-64

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY	Governor
WILLIAM L. MITCHELL	Chairman
JAMES O. GREENLEAF	Commissioner
HARRY G. WILES	Commissioner
RAYMOND B. HARVEY	Secretary
E. EDWARD JOHNSON	Gen. Counsel

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 6 - 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Ryan of Pan American has this

date requested permission to plug the following described well:

Mr. Ryan guarantees payment of the plugging fee.

Operator's full Name: Pan American Petroleum Corp.

Complete Address: Box 432, Liberal, Kansas

Lease Name: Goff Gas Unit Well No. 1

Location: 250' N. of C of NE/ 4 Sec. 8 Twp. 34 Rge. 28 (E)(W)

County Meade Total Depth 6000' Oil Well

Gas Well X Input Well  SWD Well  D & A X Lost Hole

Mr. Ryan was instructed to plug the well as follows:

- 8 5/8" to 1386' circulated w/ cement. Mud 6000' to 1410'
- Spotted 15 sacks cement 1410' to 1360' Mud 1360' to 650'
- Spotted 15 sacks cement 650' to 600' Mud 600' to 40'
- Plug, Hulls & 10 sacks cement 40' to 0'

Very truly yours,

Edgar J. Egan  
Conservation Division Agent