

State of Kansas



JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

FEB 23 1965

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION  
Wichita, Kansas

FEB 25 1965

Dear Sir:

CONSERVATION DIVISION  
Wichita, Kansas

Mr. Brown of Oil & Gas Prop. Mgt. Inc. has this

date requested permission to plug the following described well:

Mr. Brown guarantees payment of the plugging fee.

Operator's full Name: Oil & Gas Prop. Mgt. Inc.

Complete Address: 6th Floor C&I Life Bldg. Houston, Texas

Lease Name: Henry Classen Well No. # 1

Location: 1980' NSL & WEL <sup>CNE SW</sup> Sec. 1 Twp. 34S Rge. 27 (E) (W)

County Meade Total Depth 6153' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Brown was instructed to plug the well as follows:

8 5/8"-1459' Circulated w/cement.

Mud 6153' to 1410' Spotted 25 Sax.cement 1410' to 1335'

Mud 1335' to 595' Spotted 25 Sax.cement 595' to 520'

Mud 520' to 40' Plug, Hulls, 15 Sax.cement 40' to 0

Very truly yours,

Hugh Scott  
Conservation Division Agent