

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 9 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Patterson of Graham-Michaelis has this

date requested permission to plug the following described well:

Mr. Patterson guarantees payment of the plugging fee.

Operator's full Name: Graham-Michaelis Drilling co.

Complete Address: Box 1294, Liberal, Kansas 67901

Lease Name: Florence Walker Well No. 1

Location: SW SW NE Sec. 35 Twp. 34 Rge. 26 (W)

County Meade Total Depth 6111' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Patterson was instructed to plug the well as follows:

8 5/8" to 1228' circulated w/ cement. 5 1/2" to 6110' cemented.

Top perforations 5907' Plug bottom w/ 25 sacks cement.

Top of cement 5400' Mud 5400' to 700' #

Spot 35 sacks cement 700' to 600' Mud 600' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'

Very truly yours,

Conservation Division Agent