

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 7 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Morton of Texaco Inc. has this
date requested permission to plug the following described well:

Mr. Morton guarantees payment of the plugging fee.

Operator's full Name: Texaco Inc.

Complete Address: 614 Bitting Bldg., Wichita, Kansas

Lease Name: H. G. Adams Well No. 1

Location: C NE Sec. 27 Twp. 34 Rge. 29 (E) (W)

County Meade Total Depth 3345' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Morton was instructed to plug the well as follows:

13 3/8" to 40' circulated w/ cement, 8 5/8" to 444' circulated w/ cement.

2 7/8" to 3343' cemented Top perforations 3263'

Plug bottom w/ 5 sacks cement Top of cement 3100'

Mud 3100' to 450' Spotted 40 sacks cement 450' to 350'

Mud 350' to 45' Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Edgar J. Fero
Conservation Division Agent