



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 23 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Gatlin of Anadarko Production has this date requested permission to plug the following described well:

Mr. Gatlin guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Co.

Complete Address: Box 351, Liberal, Kansas

Lease Name: Fox "E" Well No. 1

Location: C NW SE Sec. 11 Twp. 34 Rge. 30 ~~(E)~~ (W)

County: Meade Total Depth 6506' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Gatlin was instructed to plug the well as follows:

- 8 5/8" to 1537' circulated w/ cement. Mud 6506.1' to 1600'
- Spot 45 sacks cement 1600' to 1450' Mud 1450' to 700'
- Spot 20 sacks cement 700' to 620' Mud 620' to 45'
- Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Edgar J. Eves
Conservation Division Agent