

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY O. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 12 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Sargent of William Gruenerwald has this
date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: William Gruenerwald & Assocs.

Complete Address: Box 909, Colorado Springs, Colorado

Lease Name: Fox Well No. 2

Location: NW NW Sec. 6 Twp. 34 Rge. 30 (E) (W)

County Meade Total Depth 6000' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1436' circulated w/ cement. 5 1/2" to 5998' Cemented

Top perforations 5627' Plug bottom w/ 25 sacks cement

Top of cement 5500' Mud 5500' to 650'

Spotted 35 sacks cement 650' to 550' Mud 550' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'

Very truly yours,

Edward J. Lynch
Conservation Division Agent