

15-119-00188-0004

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 4 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Duncan of Cotton Pet. has this

date requested permission to plug the following described well:

Mr. Duncan guarantees payment of the plugging fee.

Operator's full Name: Cotton Petroleum Corporation

Complete Address: 2121 South Columbia, Tulsa, Oklahoma 74114

Lease Name: Adams "D" Well No. 1

Location: C ~~SW~~ NE NW Sec. 25 Twp. 34 Rge. 30 <sup>YY</sup> (E) (W)

County: Meade Total Depth 5950' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Duncan was instructed to plug the well as follows:

3 3/8" to 641' circulated w/ cement. 9 5/8" to 2640' cemented.

5 1/2" to 5950' cemented. Top perforations 4600'

Plug bottom w/ 20 sacks cement to 4300' Mud 4300' to 690'

Spot 75 sacks cement 690' to 590' Mud 590' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,

Conservation Division Agent