

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 13 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Townsend of Cotton has this

date requested permission to plug the following described well:

Mr. Townsend guarantees payment of the plugging fee.

Operator's full Name: Cotton Petroleum Corporation

Complete Address: 2121 South Columbia, Tulsa, Oklahoma

Lease Name: Adams "A" Well No. 1

Location: NW NW SE SW Sec. 25 Twp. 34 Rge. 30 (E) (W)

County: Meade Total Depth 6488' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Townsend was instructed to plug the well as follows:


8 5/8" to 659' circulated w/ cement. 4 1/2" to 6116' cemented.

Top perforations 5900' Plug bottom w/ bridge Plug at 4850'

Mud 4850' to 709' Spot 50 sacks cement 709' to 575'

Mud 575' to 45' Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent