

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
DEC 18 1973
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Duncan of Cotton has this

date requested permission to plug the following described well:

Mr. Duncan guarantees payment of the plugging fee.Operator's full Name: Cotton Petroleum CorporationComplete Address: 2121 South Columbia, Tulsa, OklahomaLease Name: Adams "A" Well No. 2Location: NE NW SE SW Sec. 25 Twp. 34 Rge. 30 (E) (W)County: Meade Total Depth 5355' Oil Well Gas Well Input Well SWD Well D & A Lost Hole Mr. Duncan was instructed to plug the well as follows:8 5/8" to 999' circulated w/ cement. 5 1/2" to 5345' cemented.Open hole 5345' to 5355' Plug bottom w/ 20 sacks cement.Top of cement 4500' Mud 4500' to 1049'Spotted 50 sacks cement 1049' to 849' Mud 849' to 45'Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent