

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 18 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dublin of Underwood has this

date requested permission to plug the following described well:

Mr. Dublin guarantees payment of the plugging fee.

Operator's full Name: Underwood Oil Company Inc.

Complete Address: 420 Oil & Gas Bldg., Wichita Falls, Texas

Lease Name: Adams Well No. H-1

Location: C NE NW Sec. 23 Twp. 34 Rge. 30 (E) (W)

County: Meade Total Depth 6532' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Dublin was instructed to plug the well as follows:

16" to 92' circulated w/ cement. 8 5/8" 1533' circulated w/ cement.

4 1/2" to 6150' cemented. Top perforations 5857'

Plug to bttom w/ 20 sacks cement. Top of cement 5600'

Mud 5600' to 900' Spotted 35 sacks cement 900' to 800'

Mud 800' to 45' Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Edna J. Green
Conservation Division Agent