

15-129-10416-0000

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 22 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Hanna of Anadarko Prod. has this

date requested permission to plug the following described well:

Mr. Hanna guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Company

Complete Address: Box 351, Liberal, Kansas

Lease Name: Interstate Unit Well No. 1

Location: C SE SW Sec. 29 Twp. 34 Rge. 43 (E) (W)

County: Morton Total Depth 4255' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Hanna was instructed to plug the well as follows:

8 5/8" to 1216' circulated w/ cement, 5 1/2" to 4255' cemented.

Perforation Squeezed Off at earlier date w/ 100 sacks.cement.

Top of cement 3600' Mud 3600' to 1200'

Spot 70 sacks cement 1200' to 1000' Mud 1000' to 600'

Spot 35 sacks cement 600' to 500' Mud 500' to 50'

Plug, & 25 sacks cement 50' to 0'.

Very truly yours,

Conservation Division Agent