

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 23 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Maxey of Pioneer Prod. has this

date requested permission to plug the following described well:

Mr. Maxey guarantees payment of the plugging fee.

Operator's full Name: Pioneer Production Corporation

Complete Address: Box 2542, Amarillo, Texas

Lease Name: H.D. Roll Well No. 1

Location: C NE NE Sec. 27 Twp. 34 Rge. 43 (W)

County Morton Total Depth 4658' Oil Well

Gas Well X Input Well SWD Well D & A u Lost Hole

Mr. Maxey was instructed to plug the well as follows:

8 5/8" to 1174' circulated w/ cement. 2 7/8" to 4622' cemented.

Top perforations 4259' Plug bottom w/ 5 sacks cement.

Top of cement 4200' Mud 4200' to 600'

Spotted 35 sacks cement 600' to 500' Mud 500' to 45'

Plug, hulls & 15 sacks cement. 45' to 0'.

Very truly yours,

Edgar J. Evers
Conservation Division Agent