

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
JAN 26 1971
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jackson of Evans & Trigg has this

date requested permission to plug the following described well:

Mr. Jackson guarantees payment of the plugging fee.Operator's full Name: Evans & TriggComplete Address: 410 Woolworth Bldg., Boulder, ColoradoLease Name: Interstate Well No. 1-22Location: SW NE Sec. 22 Twp. 34 Rge. 43 (E) (W)County: Morton Total Depth 4887' Oil Well Gas Well Input Well SWD Well D & A Lost Hole Mr. Jackson was instructed to plug the well as follows:8 5/8" to 1169' circulated w/ cement. 5 1/2" to 4887' cemented.Set bridge Plug at 3960' Mud 3960' to 1200'Spot 35 sacks cement 1200' to 1100' Mud 1100' to 100'Plug & 35 sacks cement 100' to 0'

Very truly yours,

Conservation Division Agent