

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

MAR 19 1964

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Lillard of Sinclair Oil & Gas Co. has this
 date requested permission to plug the following described well:

Mr. Lillard guarantees payment of the plugging fee.

Operator's full Name: Sinclair Oil & Gas Co.

Complete Address: 311 Fidelity Bldg. Oklahoma City, Okla.

Lease Name: C.H. Tuttle Well No. # 1

Location: C NW SE Sec. 8 Twp. 35 Rge. (E) (W) 21

County Clark Total Depth 5700 Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Lillard was instructed to plug the well as follows:

13 3/8"-600' Circulated w/cement. 9 5/8"-2886' Cemented. 4 1/4"-5695' Cemented

Perforations 5590' to 5606'

Plug bottom w/7 Sax. cement top cement 5300' Mid 5300' to 600'

50 Sax. Cement 600' to 490' Mid 490' to 50'

Rock Bridge 50' to 40' 25 Sax. cement 40' to 0

Very truly yours,

Hugh Scott
 Conservation Division Agent