

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202RECEIVED
STATE CORPORATION COMMISSION

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

DEC 19 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Wasinger of Davidor & Davidor, Inc. has this date requested permission to plug the following described well:

Mr. Wasinger guarantees payment of the plugging fee.

Operator's full Name: Davidor & Davidor Inc.

Complete Address: 4515 N. Sante Fe, Oklahoma City, Oklahoma

Lease Name: Tuttle "B" Well No. 1

Location: SE NW Sec. 4 Twp. 35 Rge. 21 XX (E) (W)

County Clark Total Depth 5690' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Wasinger was instructed to plug the well as follows:

8 5/8" to 658' circulated w/ cement. 4 1/2" to 5689' Cemented.

Top Perforations 5644' Plug bottom w/ sand & 5 sacks cement.

Top of cement 5587' Mud 5587' to 600'

Spotted 30 sacks cement 600' to 500' Mud 500' to 40'

Plug, Hulls & 10 sacks cement.

Very truly yours,

Edward J. Jones
Conservation Division Agent