

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

APR 10 1963

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Davidor of Davidor & Davisor has this

date requested permission to plug the following described well:

Mr. Davidor guarantees payment of the plugging fee.

Operator's full Name: Davidor & Davidor

Complete Address: 4515 N. Santa Fe. Oklahoma City, Okla.

Lease Name: Tuttle Well No. B-1

Location: SE NW Sec. 4 Twp. 35 Rge. 21 (E) (W)

County Clark Total Depth 5760' Oil Well X

Gas Well     Input Well     SWD Well     D & A X Lost Hole    

Mr. Davidor was instructed to plug the well as follows:

8 5/8" 658' Circulated w/cement. 4 1/2" 5760' Cemented.

Top Perforations-5574' Pump 15 Sax.cement down to 5320'

Mud 5320' to 600' Plug, 35 Sax.cement 600' to 500'

Mud 500' to 40' Plug, 15 Sax.cement 40' to surface.

Very truly yours,

*Hugh Scott*  
 Conservation Division Agent