

KANSAS



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUL 20 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mobil Oil Corporation

Complete Address Box 400, Hugoton, Kansas

Lease Name Morford Well No. 1

Location App. Center Sec. 8 Twp. 34 Rge. 36 (E) (W)

County Stevens Total Depth 2859'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated None

Plugging Contractor J.D. Well Service

Address Liberal, Kansas License No. 632

Operation Completed: Hour 10:00AM Day 12 Month 7 Year 1971

The above well was plugged as follows:

10 3/4" to 709' circulated w/ cement. 7" to 2656' circulated w/ cement.

5 1/2" liner 2643' to 2859' Plug bottom w/ 70 sacks cement.

Top of cement 2000' Mud 2000' to 619'

Spotted 35 sacks cement 619' to 500' Mud 500' to 60'

Plug & 15 sacks cement 60' to 0'. Halliburton Pump Truck.

No Pipe pulled

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Charles E. Egan
Well Plugging Supervisor

DATE 7-20-71

INV. NO. 4015-W