

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 22 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Anadarko Production Company

Complete Address Box 351, Liberal, Kansas

Lease Name Interstate Unit Well No. 68

Location C SE SW Sec. 29 Twp. 34 Rge. 43 (E) (W)

County Morton Total Depth 4255'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated None

Plugging Contractor Sargents Casing Pulling Co.

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 5:50Pm Day 19 Month 6 Year 1970

The above well was plugged as follows:

8 5/8" to 1216' circulated w/ cement. 5 1/2" to 4255' cemented.

Perforations Squeezed Off at earlier date w/ 100 sacks cement.

Top of cement 3600' Mud 3600' to 1200'

Spotted 70 sacks cement 1200' to 1000' Mud 1000' to 600'

Spotted 35 Sacks cement 600' to 500' Mud 500' to 50'

Plug & 25 sacks cement 50' to 0'. Halliburton Pump Truck.

Pulled 2312' of 5 1/2" casing

I hereby certify that the above well was plugged as herein stated.

Signed: Edna A. Green
Well Plugging Supervisor

INVOICED

DATE 6/22/70
INV. NO. 2080-u