

KANSAS

Form CP-3

Rev. 6-9-67

STATE CORPORATION COMMISSION

RECEIVED  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

JUL 28 1967

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Well Plugging Authority,  
issued July 14, 1967.

RECEIVED  
CONSERVATION DIVISION  
Wichita, Kansas  
JUL 29 1967

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Cities Service Oil Company

Complete Address Box 1228, Guymon, Oklahoma 73942

Lease Name Roll "A" Well No. # 2

Location C SE NW Sec. 28 Twp. 34 Rge. 43 (E)      (W) W

County Morton Total Depth 1232'

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Halliburton Cementing Company

Address Hugoton, Kansas License No.     

Operation Completed: Hour 11:00 A.M. Day 25th Month July Year 1967

The above well was plugged as follows:

1202' of 5 1/2" long string, cement circulated with 350 sacks. 30' of open  
hole. 65 sacks of cement was pumped on bottom, with the top of the cement  
at 1060', 42 sacks of cement going into the open formation, and 23 sacks  
in the 5 1/2" long string. Hole was capped with 10 sacks of cement from 75'  
to the base of the cellar. A steel cap was welded on the 5 1/2" casing in  
the bottom of the cellar. No recovery of any pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving  
Well Plugging Supervisor

DATE 7/28/67

INV. NO. 6034-W