

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JAN 26 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Evans & Trigg

Complete Address 410 Woolworth Building, Boulder, Colorado

Lease Name Interstate Well No. 1-22

Location SW NE Sec. 22 Twp. 34 Rge. 43 (E) (W)

County Morton Total Depth 4887

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated Never Produced

Plugging Contractor Patrick Well Service

Address Liberal, Kansas License No. 630

Operation Completed: Hour 6:00PM Day 22 Month 1 Year 1971

The above well was plugged as follows:

8 5/8" to 1169' circulated w/ cement. 5 1/2" to 4887' cemented.

Set Bridge Plug at 3960' Mud 3960' to 1200'

Spotted 35 sacks cement 1200' to 1100' Mud 1100' to 100'

Spotted 35 sacks cement 100' to 0'. Halliburton Pump Truck

Pulled 1537' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 1/28/71
INV. NO. 3261-W