

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAR 19 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Sinclair Oil & Gas Co.

Complete Address: 311 Fidelity Bldg. Oklahoma City, Okla.

Lease Name C.H. Tuttle Well No. # 1

Location C NW SE Sec. 8 Twp. 35 Rge. (E) (W) 21

County Clark Total Depth 5700'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Gayle E. Toland

Address: Oklahoma City, Okla. License No. 539

Operation Completed: Hour 4 PM Day 17 Month 3 Year 64

The Above well was plugged as follows:

13 3/8"-600' Circulated w/cement. 9 5/8"-2886' Cemented. 4 1/2"-5695' Cemented.

Perforations 5590' to 5606'

Plug bottom w/7 Sax. cement top cement 5300'. Mud 5300' to 600'

50 Sax. cement 600' to 490' Mud 490' to 50'

Rock bridge 50' to 40' 25 Sax. cement 40' to 0

Pulled 4505' 4 1/2" pipe. Company Pump.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3-19-64

INV. NO. 8817-W

Signed: [Signature]  
Well Plugging Supervisor