

Form CP-3  
Rev. 6-26-62

*J.P.R.*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

APR 10 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Davidor & Davidor

Complete Address: 4515 N. Santa Fe. Oklahoma City, Okla.

Lease Name Tuttle Well No. B-1

Location SE NW Sec. 4 Twp. 35 Rge. 21 (E) (W)

County Clark Total Depth 5760'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: J.C. Wood Casing Pulling Co.

Address: Edmond, Okla. License No. ?

Operation Completed: Hour 7 PM Day 8 Month 4 Year 63

The Above well was plugged as follows:

8 5/8" 658' Circulated w/cement. 4 1/2" 5760' Cemented.

Top Perforations-5574' Pump 15 Sax.cement down to 5320'

Mud 5320' to 600' Plug, 35 Sax.cement 600' to 500'

Mud 500' to 40' Plug, 15 Sax.cement 40' to surface.

Weld cap on surface. Pulled 40 1/2' 4 1/2" pipe. (Halliburton Cementing Co.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Fugh Scott*  
Well Plugging Supervisor

DATE 4/10/63

INV. NO. 6880-u